



BERGRIVIER MUNICIPALITY

SUPPLY CHAIN MANAGEMENT

Enquiries: Tyrone April Ref: 8/3/29-2024 Tel: (022) 022 913 6000 E-mail: aprilt@bergmun.org.za

As per e-mail:

Dear Sir /Madam

NOTICE TO BIDDERS

ADDENDUM: 1

QUOTATION 8/2/36-2024 MN226-2024

THE PROVISION OF LABOUR FOR THE CONSTRUCTION OF AN ABLUTION FACILITY AT THE REDELINGHUYS CEMETERY

Pursuant to the compulsory site meeting held on Tuesday, 01 October 2024 at 12h00, at Redelinghuys Cemetery, Erf 864 Engelbrechtweg in Redelinghuys, find below the points identified for clarification.

Closing date extended till the 15th October 2024, 12H00PM. Bids to be submitted in the tender box at Municipal Offices, 13 Kerk Street Piketberg

Deletion of following line items:

- a) The setting out, the construction and finishing of an abluion facility in accordance with the approved plans attached hereto. Kindly note that the municipality will supply all the material required under this assignment, ~~unless specified otherwise in Annexure B.~~ It is an explicit agreement that the service provider will always be an independent contractor, and the appointment under this contract does not give rise to an employment contract between the municipality, the contractor, his agents, subcontractors, service providers and his/her employees.
- b) The ~~supply and~~ installation of a plastic septic tank, 5 000l and its connection with the existing wet-works ~~(To be priced on Annexure B).~~

PRICING SCHEDULE

Kindly use the pricing schedule below and attach to the tender document when submitting your bid.

Kindly note that the municipality reserves the right to reduce/vary the scope of works, in order to remain within the available budget, is not obliged to accept any bid at all, and can accept any bid either in part or in full, at its full and exclusive discretion. The inclusion of subtotal c is at the discretion of the municipality



BERGRIVIER MUNICIPALITY

TABLE 1

NR	DESCRIPTION	AMOUNT
A	INSTALLATION OF THE NEW SEPTIC TANK (RD CEMETERY). LAYING OF SLAB WITH EMBEDDED Y12 STEEL (10 X 6M) ABOVE TANK & CONNECTION TO ABLUTION FACILITY, COC	R
	VAT (15%) "A"	R
	SUBTOTAL A	R
B	THE CONSTRUCTION OF AN ABLUTION FACILITY AT THE REDELINGHUIS CEMETERY	R
	VAT (15%) "B"	R
	SUBTOTAL B	R
C	PROVISIONAL SUM (CONTINGENCIES)* (VAT INCLUSIVE)	R23 000
	FINAL BID PRICE TOTAL PRICE THAT SHOULD BE INDICATED ON THE FRONT PAGE OF THE BIDDING DOCUMENT (VAT INCLUSIVE)	SUBTOTAL A +B +C (R23 000) R

The provisional sum makes allowance for any unforeseen cost. Kindly note that the provisional sum can only be used after additional work was approved, based on a quotation, and certified as completed as such by the municipality's Project Manager.

Please indicate by ways of a tick that you agree to the specifications: -

TABLE 2

C 1 NR	DESCRIPTION	YES	NO
1	The building of the abluion facility at the RD Cemetery will include the following: - The Municipality does indicate in the specifications what they will provide (ATTACHED ANNEXURE A).	-	
2	Cast Foundations (welded mesh reinforcement in concrete surface bed, slabs, etc); 25 MPa 19 mm concrete		
3	Build out foundations; 390 X 140 X 190mm blocks in class II mortar, single skin, brick-force at every course, cavity filled with 20 MPa concrete		
4	Backfilling compacted complete (Testing where needed)		
5	Surface Bed (concrete smooth with a wooden float on DPC, and a 250 micron damp sheet laid in accordance with manufacturer's instructions)		
6	Walling complete, inclusive of doorframes, lintels, 30 x 2mm x 1m galvanised hoop iron built into walls, at a minimum of 300mm in order to anchor roof to brickwork, waterproofing with 375-micron plastic sheeting, etc. • Superstructure; 390 X 140 X 190mm blocks, single skin, brick-force every 2nd course		



BERGRIVIER MUNICIPALITY


	<ul style="list-style-type: none"> • Internal walls; 390 X 90 X 190mm blocks, single skin, brick-force every 3rd course • Blocks will be provided by the Municipality 		
7	Trusses and Roofing timbers		
8	Roof covering (including waterproofing with 4mm Torch, Silver UV paint finish, facia-boards sheeting and insulation)		
9	Plastering <ul style="list-style-type: none"> • one layer of cement on brickwork complete – Cement will be provided by Municipality 		
10	Installation of Ceilings complete with Foam Cornish		
11	Gutters & Downpipes		
12	Plumbing & Drainage (including gulleys, basins, stop-valves, urinals x 2 plus push buttons, pots and cisterns) <ul style="list-style-type: none"> • sealing of edges with approved silicone • fittings shall be jointed and sealed with butyl rubber rings • soil, waste & vent pipes shall be solvent weld jointed or sealed with butyl rubber rings • Pipes of 50mm diameter and smaller shall be plain ended with solvent welded uPVC • Pipes of 63mm diameter en greater shall have sockets and spigots with push in type integral rubber ring joints. • Bends shall be uPVC and all other fittings shall be cast iron, all with similar push in type joints • water pipework is to be disinfected at completion in accordance with SABS 1200L • Pipes shall be laid & bedded in accordance with manufacturer's instructions and carefully backfilled, and where same are absent it must be laid in accordance with the relevant SABS standards • This section includes all connections to taps, pipes, and meters, as well as excavations (not exceeding 1m), bedding, backfilling, compaction (to 95% Mod AASHTO) and disposing of excess material on site, etc. • Selected granular filling in bedding under and filling around pipes 		
13	Aluminium Windows installation + waterproofing		
14	Installation of Wooden Window Doors and Frames X9, Doors (5 hollow & 4 Meranti), plus 2 lever locks on inside doors and 3 lever lock sets on outside doors X9		
15	Canopy (installation of all woodwork, finish off with PVC gutters and fascia board)		
16	Building out & laying of apron		
17	Cleaning of Site		



BERGRIVIER MUNICIPALITY

	DESCRIPTION	YES	NO
	Legal compliance (OHSA), Insurance & Guarantees		
	Site Establishment & Temporary Fencing (minimum of 2,2m high)		
	Notice Boards & Warning Signs		
	Security provided by contractor (assumes full liability for any losses, damages, theft or any other liability that may arise)		
	Painting and Finishing 1. walls with one coat primer and two coats finishing 2. floor painted with two coat epoxy base paint 3. on wood surface two coats premium oil-based wood treatment 4. on gypsum plaster surfaces one coat primer & two coats superior quality acrylic paint 5. prime & painting of all fascia-boards 6. Prime & Painting of all ceilings 7. Prime & Painting of Doorframes & Doors X9		
	Provisional Sum (Contingencies)*	R23 000,00	
19	ATTACHED ANNEXURE A LIST OF MATERIALS		

The provisional sum makes allowance for any unforeseen cost. Kindly note that the provisional sum can only be used after additional work was approved, based on a quotation, and certified as completed as such by the municipality's Project Manager.

pp 
MUNICIPAL MANAGER

DATE: 08/10/2024

Note: Confirmation to the addendum

CONFIRMATION

I (Name and Surname of designated person) hereby declare on behalf of (Company's name),

That I take note of the above changes in the bidding documentation and that my offer will incorporate the changes.

Address:

Tel no.:

Fax no.:

Signature of bidder:

Date:

This document must be completed by the bidder (above) and submitted with his offer.