

BERGRIVIER MUNICIPALITY

SUPPLY CHAIN MANAGEMENT

Enquiries: Ms. E. Scholtz Ref: 8/3/3-2023 Tel: (022) 022 913 6038 E-mail: schottze@bergmun.org.za

As per e-mail:

Dear Sir /Madam

NOTICE TO BIDDERS

ADDENDUM: 1

TENDER 8/3/3-2023 / MN16-2023: MAINTENANCE AND REPAIR WORKS AT VELDDRIF LIBRARY


ADDENDUM NO. 1:

Pursuant to the compulsory clarification meeting held on 22 March 2023, bidders must kindly note the following:

The date for the tender submission is hereby extended until **Friday, 10 March 2023 at 12.00**. This will allow bidders ample time to access the scope of works and complete their bids in good time

ROOF

NR	ITEM	AMOUNT (VAT INCLUSIVE)
1.1	Remove existing IBR roof sheets to do necessary repairs on both sides of valley channel 15m and install extra support purlins under the roof.	R
1.2	Replace all existing roof sheet and make good (seal against water ingress,etc)	R
1.3	Replace all roof screws with class 3 timber tec screws	R
1.4	Remove existing aluminium flashing at valley channel 15m x 200mm wide	R
1.5	Replace aluminium flashing with a aluminium gutter box 250mm high x ±300mm wide aluminium gutter box 15m (see illustration)	R
1.6	Fit gutter box closer x2 and outlets x2	R
1.7	Install purlin for roof support:	R



BERGRIVIER MUNICIPALITY


	1.7.1. 152mm x50mm x15m x2 1.7.2. 56mm x76mm x15m x8 1.7.3. 228mm x 50mm x 15m x 6	R R R
1.8	Install hurricane clips and trust hangers for roof support as in no 7	R
1.9	Replace all poly closers where roof sheets was removed.	R
1.10	Install reflective insulation sheet 16mx12m x2	R
1.11	1. remove asbestos gutters outlets of down pipe and replace with aluminium gutter outlets	R

Ceiling in Velddrif Library

NR	ITEM	AMOUNT (VAT INCLUSIVE)
2.1	Remove existing ceiling in library as indicated (part of library, foyer, office, bathroom)	R
2.2	Ensure that dust sheets is erected between the two sections. Dimensions is 15mx10m to keep out the dust of operating library side.	R
2.3	Ensure that all book shelves are covered with dust sheet 25m x3m x2	R
2.4	Replace ceiling tiles with gyprex fissured 1200mmx600mm x 12.5mm	R
2.5	Ceiling dimensions for library, office, bathroom and foyer 17mx9m	R
2.6	Material: Aluminium main T and cross T in white, galvanised hanger wire	R

Light

3.1	Replace existing light	R
3.2	Remove all tube lights in library, foyer, bathroom and council office and library office	R



BERGRIVIER MUNICIPALITY

3.3	4ft LED 3 x 4 ft recessed fitting louvre VLR x 18 (excluding children side)	R
3.4	1. Replace all existing electrical wires as mentioned in point 1. Install twin and earth 2.5mm wire.	R

Electrical works

4.1	Check and replace DB board to comply with current electrical standards.	R
4.2	Replace all existing electrical work with twin and earth 2.5mm wire	R
4.3	New breakers for new light panel.	R
4.4	Supply COC on completion of electrical work. No payment will be effected without COC.	R

Children side

Ceiling


5.1	Remove existing ceiling	R
5.2	Replace with ceiling tiles(gyprex fissured 1200mmx600mm x 12.5mm) ceiling size 9mx 6m	R
5.3	Cover floor area and shelves with dust sheet. 9mx 6m x3	R

Lights

6.	Replace current lights with: 4ft LED 3 x 4 ft recessed fitting louvre VLR x 4 Install twin and earth wire 2.5mm	R
----	--	---

Replace adult light bulbs

7.	Light specifications: LEDVANCE TUBE LED ST8E 1.2M 18W 865 6500K x 45	R
----	--	---



BERGRIVIER MUNICIPALITY

Gutters

8.	1. Replace and dispose of all existing asbestos gutters and down pipes with seamless continuous aluminium gutters 65m gutter + downpipes 3,5m x6. Complete with corner angles, beads, brackets ,stop ends and outlet nozzles. A certificate of disposal must be completed after the job was done	R
----	--	---

Rahma
PP **MUNICIPAL MANAGER**

DATE: 2/3/2023

Note: Confirmation to the addendum

CONFIRMATION

I (Name and Surname of designated person) hereby declare on behalf of of (Company's name),

That I take note of the above changes in the bidding documentation and that my offer will incorporate the changes.

Address: Tel no.:
..... Fax no.:
.....

Signature of bidder: Date:

This document must be completed by the bidder (above) and submitted with his offer.